

町道湯の沢線舗装改修工事

数 量 計 算 書

令和 8 年 度

[illegible]

名 称	計 算 式			数 量
集水桝(Ⅰ型A上部)蓋調整	L	SP639.20	+50mm	
		SP651.80	+110mm	
		SP659.50	+40mm	
		SP701.30	+50mm	
		SP750.60	+50mm	
		SP801.30	+20mm	
		SP851.80	+80mm	
		SP903.20	+140mm	
		SP953.40	+40mm	
		SP1057.80	+30mm グレーチング蓋取替	
		SP1121.30	+40mm	
		SP1157.30	グレーチング蓋取替	
		SP1206.10	+60mm	
		SP1255.00	グレーチング蓋取替	
		SP1304.00	グレーチング蓋取替	
		SP1354.30	+40mm	
		SP1405.00	グレーチング蓋取替	
	R	SP640.60	+30mm	
		SP670.80	+20mm	
		SP700.50	+50mm グレーチング蓋取替	
		SP730.60	+20mm	
		SP794.80	+50mm	
		SP990.20	+20mm	
		SP1020.60	+30mm	
		SP1080.70	+50mm	
		SP1176.10	グレーチング蓋取替	
		平均	: +49mm 0.005m3/箇所	21箇所
グレーチング蓋		470×540×56		7枚
集水桝(Ⅰ型A下部)蓋調整	L	1002.70	+50mm	
		平均	: +50mm 0.005m3/箇所	1箇所

[illegible]

番号	測点名	測点間 距離[m]	幅員 [m]	施工面積 [m2]	断面積 [m2]	体積 [m3]	平均厚 [m]
0	SP620.00	0.00	7.50	0.000	0.000000	0.000	0.0000
1	SP640.00	20.00	7.50	150.000	0.267450	2.675	0.0357
2	SP660.00	20.00	7.50	150.000	0.339775	6.072	0.0453
3	SP680.00	20.00	7.50	150.000	0.287225	6.270	0.0383
4	SP700.00	20.00	7.50	150.000	0.270100	5.573	0.0360
5	SP720.00	20.00	7.50	150.000	0.269300	5.394	0.0359
6	SP740.00	20.00	7.50	150.000	0.305675	5.750	0.0408
7	SP760.00	20.00	7.50	150.000	0.252450	5.581	0.0337
8	SP780.00	20.00	7.50	150.000	0.247700	5.002	0.0330
9	SP783.20	3.20	7.50	24.000	0.265525	0.821	0.0354
10	SP800.00	16.80	7.50	126.000	0.264800	4.455	0.0353
11	SP820.00	20.00	7.50	150.000	0.308550	5.734	0.0411
12	SP840.00	40.00	7.50	300.000	0.238675	5.472	0.0318
13	SP860.00	20.00	7.50	150.000	0.283925	5.226	0.0379
14	SP880.00	20.00	7.50	150.000	0.305350	5.893	0.0407
15	SP900.00	20.00	7.50	150.000	0.252125	5.575	0.0336
16	SP919.80	19.80	7.50	148.500	0.196750	4.444	0.0262
17	SP920.00	0.20	7.50	1.500	0.206575	0.040	0.0275
18	SP940.00	20.00	7.50	150.000	0.291250	4.978	0.0388
19	SP960.00	20.00	7.50	150.000	0.271750	5.630	0.0362
20	SP980.00	20.00	7.50	150.000	0.273200	5.450	0.0364
21	SP1000.00	20.00	7.50	150.000	0.264600	5.378	0.0353
22	SP1020.00	20.00	7.50	150.000	0.304800	5.694	0.0406
23	SP1029.50	9.50	7.50	71.250	0.241275	2.594	0.0322
24	SP1040.00	10.50	7.50	78.750	0.260275	2.633	0.0347
25	SP1060.00	20.00	7.50	150.000	0.224600	4.849	0.0299
26	SP1080.00	20.00	7.50	150.000	0.285100	5.097	0.0380
27	SP1100.00	20.00	7.50	150.000	0.231900	5.170	0.0309
28	SP1120.00	20.00	7.50	150.000	0.270575	5.025	0.0361
29	SP1138.40	18.40	7.50	138.000	0.239400	4.692	0.0319
30	SP1140.00	1.60	7.50	12.000	0.271850	0.409	0.0362
31	SP1160.00	20.00	7.50	150.000	0.248775	5.206	0.0332
32	SP1175.70 (起)	15.70	7.50	117.750	0.202125	3.540	0.0270
33	SP1175.70 (終)	0.00	7.02	0.000	0.199615	0.000	0.0284
34	SP1180.00	4.30	7.02	30.186	0.183060	0.823	0.0261
35	SP1200.00	20.00	7.02	140.400	0.173680	3.567	0.0247
36	SP1220.00	20.00	7.02	140.400	0.188500	3.622	0.0269
37	SP1240.00	20.00	7.02	140.400	0.226895	4.154	0.0323
38	SP1260.00	20.00	7.02	140.400	0.208715	4.356	0.0297
39	SP1280.00	20.00	7.02	140.400	0.187525	3.962	0.0267
40	SP1300.00	20.00	7.02	140.400	0.178710	3.662	0.0255
41	SP1320.00	20.00	7.02	140.400	0.231195	4.099	0.0329
42	SP1340.00	20.00	7.02	140.400	0.211290	4.425	0.0301
43	SP1360.00	20.00	7.02	140.400	0.188310	3.996	0.0268
44	SP1380.00	20.00	7.02	140.400	0.189640	3.780	0.0270
45	SP1400.00	20.00	7.02	140.400	0.171410	3.611	0.0244
46	SP1404.60 (起)	4.60	7.02	32.292	0.119210	0.668	0.0170
47	SP1404.60 (終)	0.00	6.54	0.000	0.106770	0.000	0.0163
48	SP1420.00	15.40	6.54	100.716	0.121885	1.761	0.0186
49	SP1439.10	19.10	6.54	124.914	0.128400	2.390	0.0196
50	SP1440.00	0.90	6.59	5.931	0.134415	0.118	0.0204
51	SP1460.00	20.00	6.92	138.400	0.128675	2.631	0.0186
52	SP1463.20	3.20	6.98	22.336	0.132655	0.418	0.0190
53	SP1480.00	16.80	6.99	117.432	0.156700	2.431	0.0224
54	SP1496.10	16.10	7.01	112.861	0.194475	2.827	0.0277
55	SP1500.00	3.90	7.15	27.885	0.200600	0.770	0.0281
56	SP1503.10	3.10	7.25	22.475	0.000000	0.311	0.0000
		903.10				204.704	0.0318